



OCEAN

2026

REPORT NO. 0001
CAMDEN, NJ
OCEAN RCS

SITE FEASIBILITY REPORT

Camden Rooftop Solar + Storage

PREPARED FOR CLIENT NAME

DATE 26 SEP 2026

STATUS SAMPLE

Contents

01	SITE Roof, structure and keep-outs	03
02	SITE Electrical service and interconnection	07
03	SYSTEM Solar and storage design	10
04	ECONOMICS Production, savings and incentives	15
05	NEXT STEPS Open items, risks and schedule	20
06	APPENDIX Data sources and assumptions	22

01 SITE

Roof, structure and keep-outs

THE NEW TPO ROOF CAN CARRY A 412 KW DC ARRAY ONCE HVAC, DRAINS AND FIRE SETBACKS ARE REMOVED.

KEY FINDINGS

USABLE ROOF

68,400 FT²

ARRAY SIZE

412 KW DC

RACKING LOAD

< 5 PSF

The roof was surveyed in two passes: a drone orthomosaic for layout and a walk-down of curbs, drains and penetrations. Fire-code setbacks of 6 ft at the perimeter and 4 ft pathways between array blocks remove about 18% of the gross roof area.

The remaining usable area is about 68,400 square feet across three blocks. The structural review assumes a ballasted racking load below 5 psf; the engineer of record must confirm this against the original joist drawings before layout is frozen.



Figure 01. Roof layout context · placeholder: replace with the site survey photo before issue (evidence images must be real)

04 ECONOMICS

System summary and open risks

SIX LINE ITEMS DEFINE THE PROJECT. TWO RISKS COULD
MOVE THE SCHEDULE AND ARE FLAGGED BELOW.

ITEM	SPECIFICATION	QUANTITY	STATUS
Solar array	412 KW DC	1,030 modules	Confirmed layout
Battery storage	500 KW / 1,000 KWH	2 cabinets	Pending utility
Interconnection	2,000 A LINE-SIDE TAP	PSE&G	Application due
Roof	TPO, 20-YR WARRANTY	68,400 ft²	Complete
Incentives	ITC 30% + ADDERS	Domestic content TBC	Verify
Schedule	14 WEEKS	NTP to COD	Draft

RISK FLAGS

- ▲

UTILITY TAP APPROVAL

PSE&G may require a separate service; adds 6–10 weeks
- ▲

DOMESTIC-CONTENT EVIDENCE

Written supplier certification needed before the adder is claimed

ILLUSTRATIVE FIGURES · SAMPLE